

GRAND TRAVERSE COUNTY PUBLIC WORKS
DEPARTMENT
Grand Traverse County, Michigan

PROJ #2019369001.00

ADDENDUM #1

DATE: 12/18/2019

NOTICE: This Addendum No. 1, issued in accordance with the Contract Documents, is incorporated into the Contract Documents and supersedes and updates all conflicting information and is hereby amended in certain particulars as follows:

Date: December 18, 2019

CHANGES TO THE CONTRACT DOCUMENTS:

Advertisement for Bids.

Change Bid Schedule as follows:

Line Item No. 7, change the estimated quantity from 15 LF to 36 LF. New bid schedule attached.

CHANGES TO THE SPECIFICATIONS:

Remove SECTION 16941 INSTRUMENTATION AND CONTROLS regarding integration of generator controls and alarms into the Owner's SCADA system. The Owner will complete the system SCADA integration, monitoring, and alarm call outs, with its Contractor separate from this project. Alarms and controls included as part of the generator package and supplied by the generator manufacturer are not changed as described in the plan set.

CLARIFICATIONS:

ELECTRICAL

E1 Reference Drawing Sheet E1 – Existing Electrical Riser Diagram:

The hatched equipment shown on the existing electrical riser diagram represents equipment that is to be demolished. Disconnect and remove the existing manual transfer switch (MTS), the existing generator receptacle, and the associated conductors and conduits as shown. The existing conductors feeding the MTS from the main circuit breaker shall remain and be reconnected to the new automatic transfer switch (ATS). The existing conductors from the MTS feeding existing CB-2 and existing CB-3 shall remain and be reconnected to the new ATS. Provide and install a new cover plate on the abandoned generator receptacle junction box.

E2 Reference Drawing Sheet E1 – Proposed Electrical Riser Diagram:

Field verify the existing electrical monitoring equipment and connect the new cabling as required to monitor the new ATS as noted in the Feeder Schedule Key Note – M.

ADDENDUM ACKNOWLEDGMENT:

This Addendum No. 1 shall be attached to and shall become a part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may result in the rejection of the Bid.

END SECTION

Addendum #3
Village of Beulah Water System Improvements
12/18/2019

DISTRIBUTION: (via email)

All Plan Holders
File

BID SCHEDULE R1

I. BASE BID - ACME PUMP STATION NO. 1 GENERATOR

Item No.	Item Description	Estimated Quantity	Unit	Unit Price	Estimate Amount
1	Mobilization	1	LS		
2	Traffic Control	1	LS		
3	Soil Erosion and Sediment Control	1	LS		
4	Demolition	1	LS		
5	Generator	1	LS		
6	Concrete	1	LS		
7	Guardrail	36	LF		
8	8" Guard Posts	10	EA		
9	Site Restoration	1	LS		
TOTAL					