

PROJ #2016040001.03	ADDENDUM #1	DATE: 10/19/2017
---------------------	-------------	------------------

NOTICE: This Addendum No.1, issued in accordance with the Contract Documents, is incorporated into the Contract Documents and supersedes and updates all conflicting information and is hereby amended in certain particulars as follows:

CHANGES TO THE CONTRACT DOCUMENTS:

Section 02270, Part 3, 3.03B - Delete the following "Water all seeded areas as necessary to establish proper vegetative cover." The Contractor is not responsible for watering after planting.

CHANGES TO THE PLANS:

1. Soil erosion control fence locations and detail added (Sheets 2 and 3).
2. Identified limits of vegetation clearing within MOA property and DNR easements (Sheets 2 and 3).
3. Adjusted perforated riser top of pipe elevations (Sheet 4).
4. Added backfill of existing channel to DNR land restoration detail (Sheet 4).

GENERAL CONTRACTOR QUESTION AND CLARIFICATIONS

1. Except where stated otherwise on the drawings, the stone used as rip rap may be angular or rounded stone or crushed rock. No concrete or artificial material may be used. Local materials from existing erosion structures within the designated work areas or from unsorted stockpiles may be used.
2. Rip rap shall be placed along the entire interior embankment of each basin from the bottom toe to the discharge structure outlet elevation.
3. Seeding and fertilizer is not required on the stock pile drop site.
4. The Contractor is responsible for controlling storm water during the construction period.
5. The contractor is responsible for clearing existing vegetation as necessary within the limits shown on the drawings.
6. Detention basin berms may be constructed of onsite materials provided they are clear of rock greater than 6" diameter. Constructed berm embankments shall be compacted to 95% Modified Proctor Density.
7. Top soil is not available onsite.
8. GCES will provide initial construction staking. It is contractor's responsibility to protect the construction staking.
9. GCES will provide density testing and construction observation services for the Owner.
10. The pre-bid attendee list is attached to this addendum.

ADDENDUM ACKNOWLEDGMENT:

This Addendum No. 1 shall be attached to and shall become a part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may result in the rejection of the Bid.

END SECTION

DISTRIBUTION:

All Plan Holders (via email)
Connie Gerrie, MOA SWMA

PreBid Attendance PLAN HOLDER'S LIST

Montmorency-Oscoda-Alpena Solid Waste Management Authority Interim Storm Water Basin

Pre-Bid Meeting: 11:00 AM, October 13, 2017
 Engineer: Adam Segerlind/Gosling Czubak Engineering Sciences, Inc.
 Email: aesegerlind@goslingczubak.com

Updated: October 12, 2017
 Project No.: 2016040001.03

Plan No.	Attending Plan Holder	Company	Telephone	Email
1	Chad Crawford	Great Lakes Fusion	989-413-4110	ccrawford@greatlakesfusion.co
2	Alan Barth	Tri-County Excavating	231-347-5162	alan@triconcountyexcavating.net
3	TAD SANDBERG	SALENBIEN TRUCKING	419-446-0221	tadsalenbienexcavating.com
4	DAN LAFLECHE	TEAM ELMERS	989-657-2147	DANL@TEAMELMERS.COM
5	MARC KURTH	J+N Const.	989-732-8318	MKURTH@JAUDNINC.COM
6	RANDY WCISEL	WCISEL CONST.	989-732-4141	wciselconstruction@aol.com
7	Allen Beckman	Grade Rite Exc	989-305-9032	allen@Graderite11C.com
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				

*PDF.

*