

City of Fremont
Newaygo County, Michigan
Wastewater Lagoon Improvements

PROJ #2023755002.00	ADDENDUM #2	DATE:08/2/23
---------------------	-------------	--------------

NOTICE: This Addendum No.2, issued in accordance with the Contract Documents, is incorporated into the Contract Documents and supersedes and updates all conflicting information and is hereby amended in certain particulars as follows:

Date: August 2, 2023

CHANGES TO THE CONTRACT DOCUMENTS:

1. Section 31 05 19

DELETE Section 3.04.B – Remove entirely and replace with the following.

- B. Electric Leak Detection Survey:
Perform an electric leak detection on the newly constructed lagoon.
1. Test Standards: ASTM D6747
 2. Test Method: ASTM D7002 or
 - a. Water Puddle Method, ASTM D7002
 - b. Covered with Water or Earthen Materials, ASTM D7007
 - c. Or Engineer Approved Method
 3. Leak Detection Survey to be performed by contractor with a minimum of 50 Acres and 5 years of experience.
 4. If leaks are detected, the leak shall be found and repaired, and the lagoon shall be retested.
 5. Coordinate timing of test with construction, completion, and testing of related facilities.
 6. Provide Engineer with proposed testing schedule that is coordinated with the construction schedule.
 7. Test water may be transferred from cell to cell for testing purposes.

ADDENDUM ACKNOWLEDGMENT:

This Addendum No. 2 shall be attached to and shall become a part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may result in the rejection of the Bid.

END SECTION

DISTRIBUTION: (via email)

All Plan Holders
Todd Blake, City of Fremont
File